

# TEST REPORT

SQM\_423\_2025

CUSTOMER

**Kebe S.A.**

PRODUCT NAME

**K300PLUS**

TYPE OF PRODUCT

**Masonry unit**

TYPE OF TEST

**Determination of the thermal design conductivity of the block and of masonry made with it**

**Ordering** Kebe S.A.

**Product placed on the market from** Kebe S.A. - 61100 Nea Santa - Kilkis - GREECE

**Data related to the sample examined** Masonry unit

**Sample origin** sampled and provided from the Customer

**Manufacturing plant** Kebe S.A. - 61100 Nea Santa - Kilkis - GREECE

**Estimate** prot. 25349/lab of 06/04/2025

**Order confirmation** email of 06/04/2025

**Receipt of the samples** June 2025

**Test execution** June 2025

**Laboratory and location of test execution** Certimac - via Ravegnana, 186 - Faenza (RA)

**Report issued** 16/06/2025

**Revision n°** 01 of 25/07/2025

**Test executed by:** Eng. Mattia Morganti

**Report drafted by:** Eng. Mattia Morganti

**Approval:** Technical director Eng. L. Laghi

This document consists of n. 5 pages and cannot be reproduced partially, extrapolating parts of interest at the discretion of the customer, with the risk of favoring an incorrect interpretation of the results, except as defined in the contract. The original of this test report consists of a digitally signed electronic document in accordance with the applicable Italian legislation. Information provided by the Committee. The Laboratory declines all responsibility with respect to the nature of such information. Sampling was done by the customer. The results are verified with the sample as received.

*This test report is part of a file in PDF format  
digitally signed by Luca Laghi*

Chief Technical Officer  
(Eng. Luca Laghi)



## 1. Object of the test

The following test report describes the determination of thermal design values of a masonry brick. The calculations were performed by means of a Finite Element Model implemented in Ansys 18.2 (Ref. 2-b), applied to a planar cross section (unit length), perpendicular to the holes axis and parallel to the thermal flux. In this calculation, the input data have been modified taking into account the effect of humidity as indicated by the technical standard in Ref. 2-a.

## 2. Reference standards and documents


The tests have been executed according to the methods defined in the following documentations and reference standards:

- EN ISO 10456:2007. Building materials and products - Hygrothermal properties - Tabulated design values and procedures for determining declared and design thermal values (ISO 10456:2007)
- CertiMaC calibration report 040219-C-17/Rev01. Calibration of a two-dimensional model for the calculation of the equivalent thermal conductivity of a masonry unit.
- EN ISO 6946:2008. Building components and building elements – Thermal resistance and thermal transmittance – Calculation method.
- Test report SQM\_422\_2025 - Determination of the equivalent thermal conductivity of the block K300PLUS and of masonry made with it.

## 3. Input data

The technical drawing of the block and the thermal conductivity of fired clay were supplied by the client (Figure 1). All input data used for the calculation are shown in Tables 1 and 2.

**Figure 1.** Geometry of the block



**Table 1.** Input data

Physical quantity	Nominal value	Ref.
Material thermal conductivity $\lambda_{10, dry, mat}$	0.401 W/mK	Provided by the Customer
Equivalent thermal conductivity of voids	Test Report K300PLUS	Ref. 2-d

The adopted mortar properties refer to the product “**ORTHOBLOCK BOND**”, drawing on thermophysical data made available by the Client.

**Table 2.** Input data of the masonry

Masonry n. 1	Nominal value	Ref.
Horizontal mortar joints	Thickness = 3 mm $\lambda_{mortar} = 0.61$ W/mK	Provided by the Customer
Internal plaster	Not present	Provided by the Customer
External plaster	Not present	Provided by the Customer

#### 4. Determination of the thermal design values

Thermal design values of the masonry are determined as defined by the standards at Ref. 2-a and 2-c, increasing the thermal conductivity of the materials in relation to the moisture content, using the following conversion coefficient (moisture content volume by volume):

$$F_m = e^{f_\psi(\psi_2 - \psi_1)}$$

The standard sets as operating conditions a temperature of 23 ° C and a relative humidity of 80% (precautionary hypothesis), which is related to the test condition at 10 ° C, dry.

#### 5. Results

Table 3 shows the results of Finite Elements Analysis performed with design thermal values at Ref. 2-a.

**Table 3.** FEM results

Heat flow [W/m]	Thermal coupling coefficient $L^{2D}$ [W/mK]	Thermal transmittance $U$ [W/m <sup>2</sup> K]	Total thermal resistance $R_T$ [m <sup>2</sup> K/W]	True thermal resistance of the masonry unit $R_t$ [m <sup>2</sup> K/W]	Equivalent thermal conductivity $\lambda_{design, unit}$ [W/mK]
1.5198	0.0760	0.3040	3.2900	3.1200	0.0962

## 6. Determination of thermal values of the masonry

Table 4 shows the thermal values of the masonry, in the configuration described above.

**Table 4.** Results of the calculation for the masonry (design values)

Masonry n. 3	Result
Thermal resistance only of the layer $R_t$ [ $m^2K/W$ ]	2.8695
Equivalent thermal conductivity of the masonry $\lambda_{equ}$ [ $W/mK$ ]	0.1045
Thermal resistance of the masonry including superficial thermal resistances $R_T$ ( $m^2K/W$ )	2.8697
Thermal transmittance $U$ ( $W/m^2K$ )	0.3290

## SUMMARY TABLE OF RESULTS

The tests previously described gave the following results, taking into account the effect of humidity:

Product	Thermal design conductivity $\lambda_{equ}$ [ $W/mK$ ]	Thermal design transmittance $U$ [ $W/m^2K$ ]
Block K300PLUS	<b>0.0962</b>	<b>0.3040</b>
Masonry n. 1	<b>0.1045</b>	<b>0.3290</b>

## 7. List of distribution

ENEA	Archive	1 copy
Certimac	Archive	1 copy
Kebe S.A.	Archive	1 copy

In charged of technical test execution	In charged of technical report drafting	Technical director Approval
Eng. Mattia Morganti	Eng. Mattia Morganti	Ing. Luca Laghi
		

*This document is the exclusive property of Certimac and may not be reproduced or disclosed in any form and by any means, either wholly or partially, without having previously obtained the written permission of Certimac.*

----- End of the Test Report -----